

To: 1 041174
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 151-21,921-0000
NW SW SW, SEC. 25, T 26 S, R 12 W/E
990 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Englehardt A Well # 1

Operator: Raymond Oil Company, Inc.

County Pratt

Name & Address: P.O. Box 48788
Wichita, KS 67201

Well Total Depth 4365 141.86 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 248

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524-0209

Company to plug at: Hour: 1:30 p.m. Day: 16 Month: 5 Year: 19 96

Plugging proposal received from Darrell Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 5 1/2" at 4338' w/150 sx cement, Perfs at 4098-4123'

1st plug sand back to 4040' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 60 sx cement, 12 sx gel, 1 sx hulls, release 10 3/4"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 p.m. Day: 16 Month: 5 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4048' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 400 lbs. hulls, 10 sx gel, 60 sx cement,

12 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 150 sx cement.

Maximum pressure 650 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by United Cementing & Acid Co. Recovered 2000' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

(If applicable) observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

KANSAS CORPORATION RECEIVED 5-23-96 1996 JUN 23 11:06 AM

INVOICED

DATE JUN 05 1996
INV. NO. 45927

