

To: 1 041275
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

11-17 API NUMBER 15- 151-21,896-0000
NE NW SE, SEC. 26, T. 26 S, R. 12 W X

TECHNICIAN'S PLUGGING REPORT

Operator License / 30029
Operator: Standard Operating Company
Name: Standard Operating Company
Address: 100 N. Main, Ste. 710
Wichita, KS 67202
Lease Name: Mardis
County: Pratt
Well #: 1-26
138.16

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1997
CONSERVATION DIVISION
Wichita, Kansas

2310 feet from S section line
1650 feet from E section line
Total Depth 4251 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Mike's Testing & Salvage, Inc.
License Number: 31529
Address: P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 17 Month: 11 Year: 19 97

Plugging proposal received from: Darrell Kelso
(company name) Mike's Testing & Salvage (phone) 316-938-2943

Work: 5 1/2" at 4240' w/150 sx cement, PBTD 4200', Perfs at 4110-40'
5 1/2" casing was shot off at 2200' and started out of hole when casing parted at 160'. Attempts to fish casing were unsuccessful.

1st plug sand back to 4050' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 10 sx gel, 50 sx cement, 8 sx gel, and 125 sx cement.

Plugging Proposal Received by: Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 17 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4050' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 10 sx gel, 50 sx cement, 8 sx gel, and 125 sx cement. Maximum pressure 150 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 4% gel by Allied. Recovered 160' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did not) observe this plugging.
DATE 11-24-97
INV. NO. 49584

Signed: *Stephen J. Gierfer*
(TECHNICIAN)