

To: 1 041274  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-151-21,945 - 01-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 30029  
Operator: Standard Operating Company  
Name & Address: 100 N. Main, Ste. 710  
Wichita, KS 67202

App. NE NE SE, SEC. 26, T. 26 S, R. 12 W/4E  
2415 feet from S section line  
100 feet from E section line  
Lease Name Dutchman Well # 1  
County Pratt 160.65  
Well Total Depth 4943 feet  
Conductor Pipe: Size 13 3/8 feet 352  
Surface Casing: Size 7 5/8 feet 3708

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A   
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage License Number 31529  
Address P.O. Box 467, Chase, KS 67524

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 21 1997  
CONSERVATION DIVISION  
Wichita, Kansas

Company to plug at: Hour: 10:30 a.m. Day: Month: 11 Year: 19 97  
Plugging proposal received from Darrell Kelso

(company name) Mike's Testing & Salvage (phone) 316-938-2943

Work: 4 1/2" liner at 3605-4943' w/125 sx cement, Perfs 4243-4943', PBTD 4940'

Bottom already plugged. Kelso slickline TD @ 3100', Fluid at 300'

Spot 800 lbs. hulls, 15 sx gel, 75 sx cement, 15 sx gel, and 200 lbs. hulls, 200 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:30 a.m. Day: 17 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 7/9/97 Spotted through tubing 100 sx common cement at 4632'. Pulled tubing to 3595' and spotted 125 sx common cement. Checked cement top prior to pulling casing and found TOC @ 3100'.

11/17/97 Pumped down 13 3/8" surface pipe with 500 lbs. hulls, 15 sx gel, 75 sx cement, 15 sx gel, 300 lbs. hulls and 200 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 100 psi and shut in 0 psi.

NOV 21 1997

Remarks: Used 60/40 Pozmix 4% gel by Allied. Recovered 2000' of 7 5/8" casing.  
(If additional description is necessary, use BACK of this form for details.)

CONSERVATION DIVISION  
Wichita, Kansas

I (did) observe this plugging.

DATE 11-24-97  
INV. NO. 49585

Signed Stephen J. Berger (TECHNICIAN)