

1 050792

Continuation of 1050580 Dated 7-16-85

15-165-38405-0001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Completed 11-27-68  
C SE   , SEC. 13, T. 18 S, R. 16 W/E XX  
1320 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # \_\_\_\_\_  
Operator: Kansas Corporation Commission  
Name & Address: 200 Colorado Derby Building  
Wichita, KS 67202-1286

Lease Name Riedel Well # 1 OWWO  
County Rush  
Well Total Depth 3458 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 20" feet 70'

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number \_\_\_\_\_  
Address P. O. Box 579, Great Bend, KS 67530

Company to plug at: Hour: 4:30 pm Day: 7 Month: April Year: 19 86

Plugging proposal received from Steve Durrant  
(company name) KCC (phone) 316-225-6760

were: Halliburton pressured well with 300 psi - would not take fluid. Some leakage  
around 7" casing. Re pressured well to 525 psi. Rate established at 3 bbls per  
minute. Decided to mix cement and squeeze annular space between 7" and 15"

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:30 pm Day: 7 Month: April Year: 19 86

ACTUAL PLUGGING REPORT Pumped 200 sx Class H cement with 2% gel 3% cc. Pump  
pressure remained at 500 psi throughout squeeze. Pressure was still holding at  
375 psi after 10 minutes.

RECEIVED  
STATE CORPORATION COMMISSION

APR 15 1986  
4-15-86  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used Class H cement 2% gel 3% cc by Halliburton.  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Richard W. Lacey  
(TECHNICIAN)

15-165-3495-00 21

KCC/KDHE JOINT OIL/GAS REGULATORY OFFICE

DATE April 8, 1986

[ ] New Situation  
[ ] Response to Request  
[X] Follow-up

OPERATOR E. C. Wedell # (Deceased)

XX

NAME Responsibility for plugging given  
& to the Kansas Corporation Commission  
ADDRESS \_\_\_\_\_

LOCATION C SE, SEC 13, T 18S, R 16 W

LEASE Riedel Well # 1 OWWO

PHONE NO. \_\_\_\_\_  
OPER. \_\_\_\_\_ OTHER \_\_\_\_\_

COUNTY Rush

REASON FOR INVESTIGATION: Don Ubel, District 1 Geologist, reported this well as  
abandoned. - For further field reports - see file.

LEASE INSPECTION

PROBLEM: Well flowing

PERSON(S) CONTACTED: \_\_\_\_\_

ACTION  
~~FINDINGS:~~ 3-31-86 Dug out collar - elbow with large gate valve going into 15 1/2" ring

COMPLAINT

with cement on top. Flow-mud (new looking) and water. Checked valve for condition.  
Could not pump into well with 200 psi. Shut down - started flowing. Had pump  
truck go to 500 psi. At 300, elbow at head started leaking - shut down.  
4-7-86 Cut off elbow and chipped out cement around nipple threads. Screwed on 2"  
collar and well support plate for high pressure squeeze. Halliburton pressured well with  
300 psi - would not take fluid. Some leakage around weld and 7" casing. Repressured  
well to 525 psi. Rate established at 3 bbls per min. Decided to mix cement and squeeze.  
Pumped 200 sx class H cement with 2% gel 3% cc. Pump pressure remained at 500 psi  
throughout squeeze. After shut pressure, was still holding 375 psi in 10 minutes.

Released equipment at 6:30 pm 4-7-86. The following contractors were involved in the  
operation: \_\_\_\_\_ photos taken: \_\_\_\_\_

ACTION/RECOMMENDATIONS: Halliburton Cementing, Cheyenne Water Hauling, Garb's Welding  
Service, Holprik Dirt Service.. Location will be filled and leveled in the next  
2 days. Both wells on this section have been cut off and capped below ground level.

FIELD REPORT

Retain 1 copy Joint District Office  
Send 1 copy Conservation Division  
Send 1 copy KDHE/Topeka if appropriate

RECEIVED  
STATE CORPORATION COMMISSION

APR 15 1986  
4-15-86  
CONSERVATION DIVISION  
Wichita, Kansas

By Steve Durrant

Steve Durrant