

1 050580

15-165-30405-00-01

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 11-27-68
C SE , SEC. 13 , T 18 S, R 16 W/EX

1320 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease Name Riedel Well # 1 OWWO

Operator: Kansas Corporation Commission
Name & Address: 200 Colorado Derby Building
Wichita, KS 67202-1286

County Rush

Well Total Depth 3458 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 20" feet 70'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co., Inc. License Number _____

Address Box 31, Russell, KS 67665

Company to plug at: Hour: 12:30 pm Day: 16 Month: July Year: 19 85

Plugging proposal received from _____

(company name) _____ (phone) _____

were: 6" at 3458' PBD 2350'

Pumped 345 sx of 60/40 Pozmix 6% gel. Mixed 100 pounds of cottonseed hulls with first cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:30 pm Day: 16 Month: July Year: 19 85

ACTUAL PLUGGING REPORT Pumped 345 sx 60/40 Pozmix 6% gel with 100 pounds cottonseed hulls with first cement.

Maximum pressure 1000 psi and shut in 700 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. No recovery.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging. _____

STATE CORPORATION COMMISSION

Signed Richard W. Lacey
(TECHNICIAN)

JUL 26 1985
7-26-85

CONSERVATION DIVISION
Wichita Kansas

15-165-3445-00-01

KCC/KDHE JOINT OIL/GAS REGULATORY OFFICE

DATE July 16, 1985

[] New Situation
[x] Response to Request
[] Follow-up

OPERATOR E. C. Wedell # Deceased

NAME _____

LOCATION C SE , SEC 13 , T 18 S, R 16 W

ADDRESS Great Bend, KS 67530

LEASE Riedel Well # 1 OWWO

PHONE NO. _____
OPER. _____ OTHER _____

COUNTY Rush

REASON FOR INVESTIGATION: Don Ubel, District 1 Geologist, reported this well as abandoned.

LEASE INSPECTION

PROBLEM: Mr. Wedell has been dead for two years and left this well site abandoned.

PERSON(S) CONTACTED: The Rush County Register of Deeds and Mr. Edwin Mauler, landowner.

FINDINGS: This well was plugged on 7-16-85 using Allied Cementing's equipment. Holprik Dirt Service of Lacross dug the well head out on 7-11-85. On 7-16-85 Garb's Welding of Great Bend welded a nipple onto the wellhead. Upon completion, we connected Allied Cementing and pumped 345 sx cement using 60/40 Pozmix 6% gel for cement. Also we mixed 100 pounds of cottonseed hulls with the first few bbls of cement. We had a maximum pump pressure of 1000 psi and a shut in pressure of 700 psi. The well plugging was finished at 1:30 pm, 7-16-85. Cheyenne Oil Service hauled the fresh water.

COMPLAINT

photos taken: 0

ACTION/RECOMMENDATIONS: This well is plugged satisfactorily and the wellhead will be cut off below plow depth in the near future and the hole filled back in.

FIELD REPORT X

Retain 1 copy Joint District Office
Send 1 copy Conservation Division
Send 1 copy KDHE/Topeka if appropriate

RECEIVED By Richard W. Lacey
STATE CORPORATION COMMISSION
Richard W. Lacey

JUL 26 1985

7-26-85