

070154

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 165-20,946 - 0000  
N/2 N/2 NW, SEC. 13, T18 S, R. 16 W/EX  
4950 feet from S section line

TECHNICIAN'S PLUGGING REPORT

3960 feet from E section line

Operator License # 7671

Lease Name Mohr Well # 1

Operator: Providence Energy Corporation  
Name & Address 2700 Center, Suite 705  
2761 East Skelly Drive  
Tulsa, OK 74105

County Rush 71.50  
Well Total Depth 2200 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1024

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering License Number 5111

Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 2:00 pm Day: 17 Month: March Year: 19 86

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 4 1/2" at 2181' PBTD 2136' Perfs at 1888-94'

1st plug sand back to 1830' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 8 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 90 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 pm Day: 17 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 1830' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 8 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 90 sx cement.

Maximum pressure 1750 psi and shut in 1500 psi

Remarks: Recovered 1600' 4 1/2" casing. Used 60/40 Pozmix 6% gel 3% cc by Allied.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

observe this plugging.

STATE CORPORATION COMMISSION

Signed Dan Goodrow  
(TECHNICIAN)

DATE MAR 20 1986  
INV. NO. 13052

MAR 20 1986  
3-20-86  
CONSERVATION DIVISION  
Wichita, Kansas