

To: 1070042
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

11-25

API NUMBER 15-007-21,758 - ~~0000~~
C SW NE, SEC. 22, T 30 S, R 13 W/X
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056
Operator: F.G. Holl Company, LLC
Name & Address: P.O. Box 780167
Wichita, KS 67278-0167

Lease Name Davis S Well # 2-22
County Barber 151.78
Well Total Depth 4670 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 25 Month: 11 Year: 19 97

Plugging proposal received from Thom Pool

(company name) F.G. Holl Company, LLC (phone) 316-995-3171

4 1/2" at 4474' w/175 sx cement, Perfs: 4266-82, 4300-10, 4350-56, 4360-64'

1st plug set CIBP at 4025' with 2 sx cement on top,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 6 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:50 a.m. Day: 25 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4025' with 2 sx cement on top,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 6 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 350 psi and shut in 175 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2205' of 4 1/2" casing.

(Additional description is necessary, use BACK of this form.)

I (did / xxxxxxxx) observe this plugging.

INVOICED

DATE DEC 09 1997

INV. NO. 49602

Signed _____ (TECHNICIAN)

1-29-98
11-25 JAN 29 1998