

1 080304

P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,823-0000

C NE NE, SEC. 22, T 30 S, R 13 W/E XX

4720 feet from S section line
760 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Meand "D" Well # 1

Operator: TXO Production Corp.
Name & Address: 200 West Douglas, Suite 300
Wichita, KS 67202

County Barber 143.00

Well Total Depth 4400 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 369 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Oilfield Services License Number 5105

Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:00 am Day: 14 Month: January Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clark (phone) 316-886-5665

were: 4 1/2" set at 4394' PBD 2627' Perfs at 2523-28'

1st plug sand back to 2470' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement.

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 am Day: 14 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 2470' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 300 psi and shut in 300 psi

JAN 15 1985
1-15-85
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 1749' 4 1/2" casing. Cemented by Buie.

(If additional description is necessary, use BACK of this form.)

INVOICED

(018 / 1000) observe this plugging.

DATE 1-22-85

Signed J. A. Metz (TECHNICIAN)

INV. NO. 6634