

1 080208

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,904-0000

NW SE NW SE, SEC. 22, T 30 S, R 13 W/E
1870 feet from ~~XXX~~ SE Corner of section line
1830 feet from ~~XXX~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Davis "S" Well # 3

Operator: TXO Production Corp.

County Barber

Name & Address 200 West Douglas, Suite 300

Well Total Depth 4700 152.75 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 348

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A^X

Other well as hereinafter indicated _____

Plugging Contractor FWA Drilling Co., License Number 6165

Address Yukon, OK

Company to plug at: Hour: 4:00 pm Day: 3 Month: September Year: 19 84

Plugging proposal received from Gerald Veatch

(company name) TXO (phone) 316-265-9441

were: fo fill hole with heavy mud and spot cement through drill pipe

1st plug at 760' with 50 sx cement

2nd plug at 400' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:00 pm Day: 3 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 760' with 50 sx cement, 2nd plug at 400' with 50 sx
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate
mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1984
9-11-84
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun
(If additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

Signed J. H. Metz (TECHNICIAN) SD

DATE 9-19-84
INV. NO. 3768
9-3

OCT 12 1984