

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-21646-00-08<sup>01</sup>  
Spot: N2NWNE Sec/Twnshp/Rge: 22-30S-13W  
560 feet from N Section Line, 1980 feet from E Section Line  
Lease/Unit Name: DAVIS S Well Number: 1  
County: BARBER Total Vertical Depth: 4694 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 6427 EAST KELLOGG  
WICHITA, KS 67207

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 310 WITH 275 SX CMT  
Production: Size 4.5 feet: 4694  
Liner: Size \_\_\_\_\_ feet: \$152.56

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/04/2001 2:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: TERRY BAIRD Company: F.G. HOLL Phone: (316) 684-8481

Proposed Plugging Method: SAND TO 3900' & 4 SX CMT ON TOP. 1ST PLUG AT 650' WITH 40 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/04/2001 3:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4510'. PERFS AT 4292- 4308' & 3966-4007'. SANDED BACK TO 3900' AND PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PLUG THROUGH 4 1/2" CASING. LOAD HOLE WITH GEL. 1ST PLUG AT 650' WITH 40 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED  
DATE 6-12-01  
INV. NO. 2001061923

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 12 2001  
6-12-01  
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2845' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

JUN 05 2001

Form *CS*

*MP*