

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-14
API NUMBER 19-007-10,295-0000

C E/2 SW, SEC. 15, T. 33 S, R. 13 W
1320 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519
Operator: Chevron U.S.A. Inc.
Name & Address: P.O. Box 36366
Houston, TX 77236

Lease Name Root Well # B-2
County Barber 163.96
Well Total Depth 5045 feet
Conductor Pipe: Size feet
Surface Casing: Size 13 feet 285

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Hayes Well Service License Number 5429

Address P.O. Box 108, Attica, KS 67009

Company to plug at: Hour: 10:30 a.m. Day: 14 Month: 9 Year: 19 90

Plugging proposal received from L. Klutts

(company name) Chevron U.S.A. Inc. (phone) 713-561-3826

were: 7" at 4852' w/600 sx cement, PBSD 4792' 4 1/2" liner from 4455-5043', Perfs at 4590-4650'

Set cement retainer at 4400'. Load hole with gel. Pump 30 sx cement through retainer and put 5 sx cement on top of retainer. Perforate 7" casing at 620'. Pump down 7" casing with 220 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 a.m. Day: 14 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT Set cement retainer at 4400'. Loaded hole with gel. Pumped 30 sx cement through retainer and put 5 sx cement on top of retainer. Class A cement. Squeezed at 1800#. Perforated 7" casing at 620'. Pumped down 7" casing with 220 sx 65/35 6% gel cement at 2 BPM at 100#. Cement circulated out 7"/13" annulus.

RECEIVED STATE CORPORATION COMMISSION

SEP 20 1990

Remarks: Cemented by B.J. Services. No casing recovery. 9-20-90

(If additional description is necessary, use BACK OF THIS FORM.)

INVOICED

DATE 9-25-90

INV. NO. 29406 9-14

Signed Stephen J. Pfeifer (TECHNICIAN)