

1 040461

9-7 15-007-10297-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 13- NA  
N/2 S/2 SE, SEC. 15, T. 33 S, R. 13 W/E  
990 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519  
Operator: Chevron U.S.A. Inc.  
Name & Address: P.O. Box 36366  
Houston, TX 77236

Lease Name Holmes Well # C-2  
County Barber 159.64  
Well Total Depth 4912 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 13 feet 272

Abandoned Oil Well Gas Well  Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Dunnam Well Service License Number 9678

Address 130 W. Pancake, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 7 Month: 9 Year: 19 90

Plugging proposal received from L. Klutts

(company name) Chevron (phone) 713-561-3826

were: 7" at 4837' w/550 sx cement, PBSD 4908', Perfs at 4872-87', 4 1/2" liner from 4480-4911'

Set cement retainer at 4450', displace hole with gel, pump 40 sx cement through retainer,  
Pull out of retainer and put 10 sx cement on top of retainer. Lay tubing down. Perforate

7" casing at 620'. Set cement retainer at 519'. Pump through cement retainer with 90  
sx lite cement. Lay down tubing. Perforate 7" casing at 250'. Pump 137 sx lite cement  
down 7" casing.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 3 p.m. Day: 7 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT Set cement retainer at 4450' and displaced hole with gel. Pumped

40 sx cement through retainer. Pulled out of retainer and put 10 sx cement on top of  
retainer-Class A cement. Layed down tubing. Perforated 7" casing at 620'. Set cement  
retainer at 519'. Pumped through cement retainer with 90 sx Halliburton lite cement 6% gel.  
(75 sx cement were squeezed out perfs at 620') Maximum pressure 450 psi and shut in 250 psi.  
Layed down tubing. Perforated 7" casing at 250'. Pumped 137 sx Halliburton lite cement  
w/6% gel down 7" casing. Cement circulated. Rate=5 BPM at 150#.

Remarks: Cemented by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-25-90

INV. NO. 29412

9-7

Signed *Stephen J. Pfeifer* (TECHNICIAN)

SEP 18 1990  
7-18-90