

1 040459

9-5

API NUMBER 15- NA 15-007-00637-00-02

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C E/2 SE, SEC. 15, T 33 S, R 13 W/E

1320 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519

Lease Name Holmes Well # C-1

Operator: Chevron U.S.A. Inc.

County Barber 158.24

Name & Address P.O. Box 36366

Well Total Depth 4869 feet

Houston, TX 77236

Conductor Pipe: Size _____ feet

Surface Casing: Size 13 feet 315

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Dunnam Well Service License Number 9678

Address 130 W. Pancake, Liberal, KS 67901

Company to plug at: Hour: 9 a.m. Day: 5 Month: 9 Year: 19 90

Plugging proposal received from L. Klutts

(company name) Chevron (phone) 713-561-3826

were: 7" at 4504', 5 1/2" liner from 4630-4840'/35 sx cement, 4 1/2" liner from 4401-4691'

Perfs = Mississippi 4520-4630', Misener 4851-67'

1st plug set cement retainer at 4350', displace hole from 4350' to 600' w/gel, sting into retainer, pump 50 sx cement through retainer, pull out of retainer and put 10 sx cement on top of retainer. Lay down tubing, perforate 7" casing at 620', pump down 7" casing with 280 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 5 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug set cement retainer at 4350', displaced hole from 4350' to 600' with gel, stung into retainer, pumped 50 sx cement through retainer. Pulled out of retainer, and put 10 sx cement on top of cement retainer. Cemented with Class A cement.

2nd plug layed down tubing. Perforated 7" casing at 620', pumped down 7" casing with 280 sx Halliburton lite w/6% gel. Cement circulated between 7"/13" surface pipe annulus.

Maximum pressure 200 psi.

Remarks: Cemented by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

Do not observe this plugging.

INVOICED

DATE 9-25-90

INV. NO. 29411

9-5

Signed Stephen J Pfeifer
(TECHNICIAN)

SEP 18 1990
9-18-90