

1 010145

15-067-03343-00-01

Docket No. E-19,059

API NUMBER 13- Completed 6-30-39

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

875' N of C NESEC. 1535, T 33 S, R 13 W

4835 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519

Lease Name Holmes "C" Well # 3 SWD

Operator: Chevron U.S.A., Inc.

County Barber 158.24

Name & Address P. O. Box 12116

Well Total Depth 4869 feet

Oklahoma City, OK 73157

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Chevron U.S.A., Inc. License Number 4519

Address P. O. Box 12116, Oklahoma City, OK 73157

Company to plug at: Hour: 8:00 am Day: 12 Month: June Year: 19 86

Plugging proposal received from Randy English

(company name) Chevron (phone) 405-949-7049

were: 7" at 4833' Perfs at 4553-4600'

1st plug run tubing to 4790' with 2 sx hulls and 150 sx cement. Wait 1 1/2 hours & tag plug.

2nd plug circulate 150 bbls 9# mud and perforate at 750' and pump 350 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:30 pm Day: 12 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug ran tubing to 4790' and pumped 2 sx hulls and 150 sx

Class H cement with 1% cc. Tagged cement at 4140'. Ran tubing and pumped 150 bbls of

8.6 lbs mud. Pulled tubing. Great Guns perforated 4 shots at 750'. Pumped 400 sx

Did not circulate. ^{between} 7" and 10 3/4" took 65 sx to surface.

RECEIVED STATE CORPORATION COMMISSION JUN 23 1986 6-23-86 CONSERVATION DIVISION Wichita, Kansas

Remarks: Used Class H 1% cc by Halliburton. (If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

INVOICED DATE JUN 23 1986 INV. NO. 14187