

1 051368

11-16

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-22,017-00-00

SE NW SW, SEC. 19, T 26 S, R 13 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435

Operator: Bowers Drilling Company, Inc.

Name & Address 125 N. Market, Suite 1425

Wichita, KS 67202

1650 feet from S section line

4290 feet from E section line

Lease Name McMannis Well # 1

County Pratt 145.50

Well Total Depth 4477 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well Gas Well Input Well SMD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour 9 p.m. Day: 16 Month: 11 Year: 19 90

Plugging proposal received from Harvey Moore

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 869-882'

1st plug at 890' with 50 sx cement, 2nd plug at 350' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30 p.m. Day: 16 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 890' with 50 sx cement,

2nd plug at 350' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement,

Water well plugged with 10 sx cement.

Remarks: Used 60/40 Pozmix, 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED I did not observe this plugging

DATE NOV 27 1990

INV. NO. 30027

RECEIVED STATE CORPORATION COMMISSION

RECEIVED STATE CORPORATION COMMISSION

Signed Richard W. Lacey (TECHNICIAN)

NOV 26 1990 11-26-90