

To: 1 090777 2-14
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-119-20,855-0001
S/2 SW SE, SEC. 13, T 32 S, R 30 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

330 feet from S section line
1980 feet from E section line
Lease Name Fox "G" Well # 1
County Meade 198.25
Well Total Depth 6100 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1621

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10:30 a.m. Day: 14 Month: 2 Year: 19 97

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

Work: 5 1/2" at 5754' w/150 sx cement, PBTD 5752, Perfs at 5609-30(squeezed), 5655-69'
1st plug pump 2 sx hulls and 25 sx cement on bottom,
2nd plug pump 30 sx cement at cutoff,
3rd plug pump 50 sx cement at 1650',
4th plug pump 40 sx cement at 650', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 2:30 p.m. Day: 14 Month: 2 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement on bottom,
2nd plug loaded hole with mud and spotted 30 sx cement at 2475',
3rd plug pulled to 1630' and spotted 50 sx cement,
4th plug pulled to 650' and spotted 40 sx cement,
5th plug filled with 10 sx cement from 40-0'.

RECEIVED
KANISAS CORP COMM
1997 FEB 18 P 3:20
2-18-97

Remarks: Used common cement by Sargent & Horton. Recovered 2502' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (Name) observe this plugging.

INVOICED
DATE 2-19-97
INV. NO. 47592
2-14

Signed [Signature] (TECHNICIAN)