

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-20877-00-00  
Spot: SWNENW Sec/Twnshp/Rge: 36-34S-15W  
990 feet from N Section Line, 1650 feet from W Section Line  
Lease Name: DAVIS RANCH Q Well #: 2  
County: BARBER Total Vertical Depth: 4950 feet

Operator License No.: 34941  
Op Name: BLESSED OPERATING LLC  
Address: 302 W. CENTRAL AVE.  
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4780		WITH 2 SX CMT
PROD	5.5	4949	0	WITH 200 SX CMT
SURF	10.75	276		WITH 250 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/05/2014 8:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: ALAN VRATIL Company: \_\_\_\_\_ Phone: (620) 886-2419

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 09/11/2014 2:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 4780' WITH 2 SX CMT. 9/5/14: 1ST PLUG AT 1276' WITH 25 SX COMMON CMT WITH 3% CC. WAITED 1 HOUR & TAGGED CMT AT 1000'. PERFORATED AT 600' & PUMPED 300 SX CMT. DID NOT CIRCULATE. 9/11/14: RAN LINE AND FOUND CMT AT 160'. TOPPED OFF WITH 20 SX CMT. PUMPED DOWN BACKSIDE WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4821	4856		

Received  
KANSAS CORPORATION COMMISSION

SEP 26 2014

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

*Michael J. Maier*  
(TECHNICIAN)

10/1/14 CKM

RECEIVED  
SEP 12 2014  
KCC DODGE CITY