

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20925-00-01
Spot: SE Sec/Twnshp/Rge: 30-22S-31W
1307 feet from S Section Line, 1301 feet from E Section Line
Lease Name: RUSSEL Well #: 1-30
County: FINNEY Total Vertical Depth: 4970 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2919	0	WITH 575 SX CMT
SURF	8.625	1299		WITH 600 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/04/2014 1:30 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 90 SX CMT WITH 200# HULLS. DISPLACE WITH WATER TO 1400'. TEST CASING TO 700#. RUN CBL TO DETERMINE TOC. PERFORATE AND/OR RUN TBG AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/04/2014 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 90 SX CMT WITH 200# HULLS DOWN 4 1/2" CASING. DISPLACE WITH WATER TO 1350'. TEST CASING TO 500#. HOLDING. RUN CBL FROM 1400' TO 20'. TOC BEHIND 4 1/2" CASING AT 475'. PERFORATE 4 HOLES AT 380'. RUN TBG TO 1300' & FILL 4 1/2" CASING WITH CMT UP TO 300' USING 90 SX CMT. TOOH WITH TBG & HOOK UP TO 4 1/2" CASING & CIRCULATE CMT FROM THE PERFS AT 380' TO 0' WITH 80 SX CMT, LEAVING THE 4 1/2" CASING AND 4 1/2" X 8 5/8" ANNULUS FULL OF CMT. TOP OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2700	2710		

Received
KANSAS CORPORATION COMMISSION
SEP 26 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLDIATED.

Plugged through: TBG

District: 01

Signed _____

Ken Jehlik
(TECHNICIAN)

10/1/14 ccm

SL

RECEIVED
SEP 16 2014
KCC DODGE CITY