

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20926-00-01  
Spot: SWSENESE Sec/Twnshp/Rge: 16-22S-31W  
1346 feet from S Section Line, 530 feet from E Section Line  
Lease Name: WINTERS Well #: 2-16  
County: FINNEY Total Vertical Depth: 4975 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2798	0	WITH 520 SX CMT
SURF	8.625	1303		WITH 600 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/04/2014 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 85 SX CMT WITH 200# HULLS. DISPLACE WITH WATER TO 1400'. TEST CASING TO 700#. RUN CBL TO DETERMINE TOC. RUNG TBG AND/OR PERFORATE AS NECESSARY.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/04/2014 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMPED 85 SX CMT WITH 200# HULLS VIA 4 1/2" CASING. DISPLACE WITH WATER TO 1400'. TEST CASING TO 700#. HOLDING: RUN CBL FROM 1400' TO 20'. TOC BEHIND 4 1/2" CASING IS 215'. RUN TBG TO 1425' & FILL THE 4 1/2" CASING WITH CMT TO SURFACE WITH 105 SX CMT. TOOH WITH TBG. TOP OFF 4 1/2" CASING WITH 15 SX CMT. PUMP 15 SX CMT DOWN THE ANNULUS TO 400#.

Perfs:

Top	Bot	Thru	Comments
2698	2708		

Received  
KANSAS CORPORATION COMMISSION  
**SEP 26 2014**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

*Ken Jehlik*  
10/1/14 CKM  
(TECHNICIAN)

RECEIVED  
SEP 16 2014  
KCC DODGE CITY