

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03260-00-00
Spot: NESE Sec/Twnshp/Rge: 5-16S-12W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: POLZIN Well #: 1
County: BARTON Total Vertical Depth: 3300 feet

Operator License No.: 4871
Op Name: CURT'S OIL OPERATIONS LLC
Address: PO BOX 8
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3296		150 SX
SURF	8.625	261		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/05/2014 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CURT'S OIL Phone: (620) 793-2540

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 500 # hulls and 7 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/05/2014 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1450', 768' and 250'. Ran tubing to 2790' and pumped 7 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1700' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 700'. Circulated cement to surface on casing and surface pipe w/160 sx cement and 150 # hulls. Pulled tubing. Topped off w/10 sx cement.

GPS: 38.68719 -098.66622

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

SEP 23 2014

RECEIVED
KANSAS CORPORATION COMMISSION

10/1/14 CLKM

Form CP-2/3

SEP 29 2014

CONSERVATION DIVISION
WICHITA, KS