

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22221-00-00
Spot: E2NESW Sec/Twnshp/Rge: 10-28S-13W
1980 feet from S Section Line, 2970 feet from E Section Line
Lease Name: YOUNG Well #: 1
County: PRATT Total Vertical Depth: 4451 feet

Operator License No.: 34764
Op Name: JUMPING LEAF LLC
Address: 1416 WESTERN AVE. PO BOX 396
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3950		WITH 2 SX CMT
COND	13.375	131		
PROD	5.5	4485	2024	WITH 150 SX CMT
SURF	8.625	346		WITH 200 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/25/2014 9:00 AM
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 09/01/2014 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 3950' WITH 2 SX CMT. 8/25/14: 1ST PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. DID NOT CIRCULATE. 2ND PLUG AT 380' WITH 50 SX CMT. DID NOT CIRCULATE. 3RD PLUG AT 40' WITH 10 SX CMT. COULD NOT LOAD HOLE 9/1/14: TOPPED OFF WITH 3 YARDS REDIMIX.

Perfs:

Top	Bot	Thru	Comments
4300	4312		
4255	4258		
4250	4252		
4004	4010		
3878	3880		

Received
KANSAS CORPORATION COMMISSION

SEP 26 2014

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

10/1/14 cpm

RECEIVED

SEP 16 2014

KCC DODGE CITY

Form CP-2/3