

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-00296-00-00
Spot: NESWNW Sec/Twnshp/Rge: 2-18S-14W
1550 feet from N Section Line, 990 feet from W Section Line
Lease Name: EVELEIGH Well #: 1
County: BARTON Total Vertical Depth: 3396 feet

Operator License No.: 7023
Op Name: KLIMA WELL SERVICE, INC.
Address: PO BOX 48
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3381		125 SX
SURF	8.625	184		192 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/05/2014 3:00 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS KLIMA Company: KLIMA WELL SERVICE, INC. Phone: (620) 793-8888

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 12 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/05/2014 7:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran tubing to 3200' and pumped 12 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1500' and pumped 65 sx cement w/200 # hulls. Pulled tubing to 870'. Circulated cement to surface with 110 sx cement. Pulled tubing. Topped off w/20 sx cement.

GPS: 38.51101 -098.84528

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

10/1/14 CKM

SEP 17 2014

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 29 2014

CONSERVATION DIVISION
WICHITA, KS