

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20981-00-00
Spot: NESENW Sec/Twnshp/Rge: 2-18S-14W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: TINDALL Well #: 1
County: BARTON Total Vertical Depth: 3350 feet

Operator License No.: 7023
Op Name: KLIMA WELL SERVICE, INC.
Address: PO BOX 48
GREAT BEND, KS 67530

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comments</u>
PROD	4.5	3348		150 SX
SURF	8.625	816		425 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/17/2014 8:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS KLIMA Company: KLIMA WELL SERVICE, INC. Phone: (620) 793-8888

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/17/2014 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran tubing to 3150' and pumped 120 sx cement. Pulled tubing to 1500' and pumped 50 sx cement. Pulled tubing to 800' and pumped 30 sx cement. Pulled tubing to 400'. Circulated cement to surface with 25 sx cement. Pulled tubing. Topped off w/30 sx cement. Tied on to backside and pressured up to 200 psi. Held pressure w/5 sx cement.

GPS: 38.51669 -098.84062

Remarks: QUALITY WELL SERVICE

Plugged through: TSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

SEP 22 2014

RECEIVED
KANSAS CORPORATION COMMISSION

10/1/14 CKM

Form CP-2/3

SEP 29 2014

CONSERVATION DIVISION
WICHITA, KS