

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20343-00-00  
Spot: SW Sec/Twnshp/Rge: 14-25S-31W  
1339 feet from S Section Line, 3672 feet from E Section Line  
Lease Name: WELDON Well #: 1-14  
County: FINNEY Total Vertical Depth: 2593 feet

Operator License No.: 9152  
Op Name: MAREXCO, INC.  
Address: 3033 NW 63RD ST - STE 151  
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1046		WITH 2 SX CMT
PROD	4.5	2593	0	WITH 200 SX CMT
SURF	8.625	369		WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/08/2014 4:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 2500' WITH 2 SX CMT OR 25 SX CMT WITH 150# HULLS. CIBP @ 1050'. TEST CASING TO 700#. PERFORATE 4 HOLES AT 1000'. ESTABLISH INJECTION RATE THROUGH PERFS WITH WATER. PUMP 80 SX CMT 1/2 IN & 1/2 OUT OF PERFS WITH HULLS IN LAST HALF. PERFORATE 4 HOLES AT 400'. CIRCULATE CMT TO SURFACE LEAVING CASING & ANNULUS FULL OF CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/08/2014 7:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SAND BACK TO 2490' & CAP WITH 4 SX CMT. CIBP @ 1046' WITH 2 SX CMT. TEST CASING TO 700#. HOLDING. PERFORATE 4 HOLES AT 1000'. INJECTION RATE 1 1/2 BPM AT 300#. PUMP 60 SX CMT & DISPLACE WITH 9 BBL WATER, LEAVING 30 SX CMT OUTSIDE THE CASING & 30 SX CMT INSIDE THE CASING. PERFORATE 4 HOLES AT 390'. CIRCULATE CMT TO SURFACE USING 135 SX CMT, LEAVING THE 4 1/2" CASING AND 4 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2562	2570		

Received  
KANSAS CORPORATION COMMISSION  
**SEP 26 2014**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Ken Jehlik  
(TECHNICIAN)

RECEIVED  
SEP 16 2014  
KCC DODGE CITY

10/1/14 CKM