

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20816-00-00
Spot: W2W2W2SE Sec/Twnshp/Rge: 9-25S-31W
1320 feet from S Section Line, 2530 feet from E Section Line
Lease Name: REED Well #: 2-A
County: FINNEY Total Vertical Depth: 2603 feet

Operator License No.: 9152
Op Name: MAREXCO, INC.
Address: 3033 NW 63RD ST - STE 151
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2154		WITH 2 SX CMT
PROD	4.5	2596	1744	WITH 170 SX CMT
SURF	8.625	1766		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/04/2014 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 09/04/2014 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

****LEFT 300' OF RODS & 300' OF 2 3/8" TBG IN HOLE**** CIBP @ 2154' WITH 2 SX CMT. 1ST PLUG RUN TBG TO 1824' & SPOT 50 SX CMT IN AND OUT OF THE STUB. 2ND PLUG AT 1097' WITH 50 SX CMT. 3RD PLUG AT 420' WITH 50 SX CMT. 4TH PLUG AT 32' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2518	2528		

Received
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

SEP 26 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

10/1/14 CKM

SP

RECEIVED

SEP 16 2014

KCC DODGE CITY