

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22076-00-01
Spot: NESENW Sec/Twnshp/Rge: 14-30S-14W
1650 feet from N Section Line, 2310 feet from W Section Line
Lease Name: MCKENZIE Well #: 3
County: BARBER Total Vertical Depth: 4854 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4831		350 SX
SURF	8.625	304		200 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/11/2014 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 35 SX CMT WITH 250# HULLS ON BOTTOM. PLUG AT 780' WITH 10 SX GEL & 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 09/11/2014 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 30 SX CMT WITH 200# HULLS AT 4200'. 1ST PLUG AT 780' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 240' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4486	4496		
4470	4480		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION

SEP 26 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Ken Jehlik
(TECHNICIAN)
10/1/14 CKM

RECEIVED

SEP 16 2014

KCC DODGE CITY