

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-20829 0000

LEASE NAME Roadie A

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

330' FSL
SPOT LOCATION 330' FW of SW/4

SEC. 3 TWP. 34 RGE. 22 ~~W~~ (W)

COUNTY Clark

Date Well Completed 8-24-84

Plugging Commenced 8-24-84

Plugging Completed 8-24-84

LEASE OPERATOR Cities Service Oil & Gas Corporation

ADDRESS 3545 N. W. 58th Street, Okla. City, OK 73112

PHONE # (405) 949-4400 OPERATORS LICENSE NO. 5447

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City Office, Dist. I

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation --- Depth to top --- bottom --- T.D. 5575'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cherokee & Chester	Dry	5165	5390	8 5/8"	908'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 8-24-84: Ran OE DP and set following Class H cmt OH plugs: 35 sx 5430' - 5530' Chester; 35 sx from 3450-3550' Topeka; 35 sx from 859-959' Base surf.; 35 sx from 450-550' Mid Surf.; 10 sx from 40-4' Top plug; 10 sx mouse & rate Hole. P & completed & released rig at 10 a.m. 8-24-84.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. B. Bhannan Drilling, Inc. License No. 5879'

Address 2324 North Highway 83

Liberal, Kansas 67901

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del Oliver (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well **RECEIVED** that the same are true and correct, so help me God. STATE CORPORATION COMMISSION

(Signature) Del Oliver

(Address) 3545 N. W. 58th Street, Okla. City, Okla. 73112

SUBSCRIBED AND SWORN TO before me this 28 day of August, 1984
Wichita, Kansas

Joyce A. Barber
Notary Public

My Commission expires: 6-12-88