

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-30367-0000
API NUMBER 17-30-86

LEASE NAME Stephens

WELL NUMBER B-7
Approx. 4290 Ft. from S Section Line
Approx. 2310 Ft. from E-Section Line

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rains & Williamson Oil Co. Inc.
ADDRESS 435 Page Court, 220 West Douglas, Wichita, Kan.
PHONE (316) 265-9686 OPERATORS LICENSE NO. 5146

SEC. 33 TWP. 15s RGE. 20 (E or W)

COUNTY Ellis

Date Well Completed 7-30-86

Plugging Commenced 7-11-86

Plugging Completed 7-11-86

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Conglomerate Sand Depth to Top 3985 Bottom 3987 T.D. 3987

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Conglomerate Sand	Oil	3985	3987	5 1/2	3985	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

B-J Titan On 8 3/4 no cement, instant pressure of 1000 lbs. Down 5 1/2 with 50 sk. thirty mix followed with 95 sk. hulls mixed in 50 sk. cement, followed with 100 sk. cement. Max. pressure 800 lbs. Shut in at 460 lbs. State agent Marion Schmidt.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Paul Stephens License No. 683

Address P.O. Box 166

STATE OF Kansas COUNTY OF Pratt, ss.


Rains & Williamson Oil Co. Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul Stephens

(Address) Box 166, Pratt, Ks 67124

SUBSCRIBED AND SWORN TO before me this 15 day of August, 19 86

Juanita M. Green
Juanita M. Green Notary Public



Commission Expires: 10-4-87

AUG 5 1986

08-05-86

STENCILED

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
308 EAST MURDOCK - WICHITA, KANSAS

ORIGINAL

SEP 24 1966

COMPANY COLORADO OIL

SEC. 33 T. 15 R. 20W
LOC. SW NW NE

FARM Stephens

NO. 1

COUNTY Ellis

KANSAS

TOTAL DEPTH 3989

COMM. 7-14-66


COMP. 7-30-66

SHOT OR TREATED

CONTRACTOR Rains & Williamson Oil

ISSUED 9-24-66

K. G. S. LIBRARY



CASING

20

10

15

8 5/8"

@ 269.65' w/170 SX.

ELEVATION 2258' KB

12

6

13

5 1/2"

@ 3988' w/650 SX.

PRODUCTION ST TST:

FMP 127 BOPD, 6% Wtr
(Comp 3965-68)

FIGURES INDICATE BOTTOM OF FORMATIONS

FORMATIONS

TOPS: SCOUT

Surface Soil & Clay	40'
Shale	515'
Sand	580'
Sand & Shale	955'
D. Sand	1170'
Shale	1496'
Anhydrite	1536'
Shale	2155'
Lime & Shale	3547'
Lime	3950'
Shale & Sand	3987'
Total Rotary Depth	3987'

*Anhydrite	1496-1536
Heebner	3529
Lansing	3573
Base Kansas City	3826
Marmaton	3894
Conglomerate Shale	3946
" Sand	3964
Reag Sand	3985

MAR 21 1965

CONSERVATION DIVISION
Wichita, Kansas