

Commission

Mary Walsh #1
SW SE SE of Section 1-27S-12W
Pratt County, Kansas
Mid-Continent Petroleum Corporation

Location made by Lloyd Snyder: Oct. 18, 1943
Commenced: Oct. 26, 1943
Completed: Nov. 20, 1943

Sand	0	65	
Sand and shells	65	190	
Red bed and shale	190	415	
Red rock	415	455	Set 8 5/8" surface casing at 444 below rotary table
Shells and shale	455	545	
Red bed	545	585	
Anhydrite	585	610	
Red bed	610	660	
Shale and shells	660	1130	
Shale	1130	1625	
Sandy Lime	1625	1880	
Lime	1880	1945	
Sandy Lime	1945	2135	
Lime	2135	2630	
Shale and Lime	2630	2820	
Shale	2820	2900	
Lime	2900	3045	
Shale	3045	3170	
Lime - Topeka	3170	3620	Topeka at 3170'
Shale	3620	3675	
Lime - Brown K.C.	3675	3700	Brown Lime at 3675'
Lime - White K.C.	3700	3962	White K.C. Lime at 3700'
Shale	3962	3973	
Lime	3973	4020	
Shale	4020	4050	
Broken Lime	4050	4090	
Lime	4090	4115	
Shale	4115	4148	
Chert and Shale	4148	4165	Top of Chat 4148'
Sand	4165	4171	
Chert and Shale	4171	4193	Kinderhook at 4180'
Lime	4193	4240	
Lime and Shale	4240	4338	
Viola Lime	4338	4377	Top of Viola 4338'
Simpson Shale	4377	4428	Top of Simpson Shale 4377'
Simpson Dolomite	4428	4453	Top of Simpson Dolomite 4428'
Shale green	4453	4519	
Arbuckle Lime	4519	4570	Top of Arbuckle 4519' Total Depth. No porosity. No show of oil or gas. Abandoned report attached.

PLACING
FILE NO. 1-27-12W
BOOK PAGE 100 LINE 18

STATE OF KANSAS)
 ss
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of our Mary Walsh Well #1, located in the Southwest Quarter of the Southeast Quarter of the Southeast Quarter of Section 1, Township 27 South, Range 12 West, Pratt County, Kansas.

MID-CONTINENT PETROLEUM CORP.

By Lloyd Snyder
Superintendent

Subscribed and sworn to before me, a Notary Public, this 23rd day of November, 1943.

My commission expires 11-5-46 Rachel Perry Notary Public

NOV 23 1943