

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,802-00-00

LEASE NAME Lathrop

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER A-7

4120 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 3 TWP. 27 RGE. 12 ~~XX~~ or (W)

COUNTY Pratt

LEASE OPERATOR D & D Production, Inc.

ADDRESS 403 S. Main, Box 321 Pratt, KS 67124

PHONE# (316) 672-5002 OPERATORS LICENSE NO. 9514

Date Well Completed 9-23-86

Character of Well D&A

Plugging Commenced 9-24-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-24-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City  
to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4430'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Bottom Plug: @ 690' w/ 50 sacks cement thru drill pipe

Next Plug: @ 330' w/ 40 " " " " " " " " " " " "

Top Plug: @ 40' w/ 10 sacks cement 15 sacks in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 25 day of September, 19 86

RECEIVED  
STATE CORPORATION COMMISSION  
CONS. DIV. WICHITA, KS

Dorothy M Hague  
Notary Public



Commission Expires: \_\_\_\_\_

SEP 26 1986

DRILLER'S WELL LOG

DATE COMMENCED: Septebmer 17, 1986  
DATE COMPLETED: September 23, 1986

D & D Production, Inc.  
LATHROP A-7  
Approx. C S/2 NE NW  
Sec. 3, T27S, R12W  
Pratt County, Ks.

ELEVATION: 1904 K.B.

0 - 677' Surface Soil, Shale, Sand  
677 - 691' Anhydrite  
691 - 3576' Shale & Lime  
3576 - 3581' Shale  
3581 - 3617' Lime & Shale  
3617 - 3770' Shale  
3770 - 3788' Lime & shale  
3788 - 4163' Lime  
4163 - 4430' Chert & lime  
4430' RTD

FORMATION DATA

Anhydrite 677'  
Heebner 3576'  
Douglas 3617'  
Br. Lime 3770'  
Kansas City 3788'  
Base K.C. 4163'  
Mississippi 4383'  
RTD 4430'

Surface Pipe: Set new  
8-5/8", 20# pipe @300'  
w/225 sacks 60/40 pozmix  
2% gel 3% cc.


A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the fact and statements herein are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 25 day of September 1986.



*Dorothy M. Hague*  
Notary Public

RECEIVED  
D & D PRODUCTION COMPANY  
PRATT, KANSAS

SEP 26