

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER ¹⁵¹ 15-121-21,793-00-00

LEASE NAME Lathrop

WELL NUMBER A-6

2510 Ft. from S Section Line

3930 Ft. from E Section Line

SEC. 3 TWP. 27 RGE. 12 (X) or (W)

COUNTY Pratt

Date Well Completed 6-25-86

Plugging Commenced 6-25-86

Plugging Completed 6-25-86

LEASE OPERATOR D & D Production, Inc.

ADDRESS 403 S. Main, Box 321 Pratt, KS 67124

PHONE# (316) 672-5002 OPERATORS LICENSE NO. 9514

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Steve Durrant

Is ACO-1 filed? operator to be filed by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 1050' w/50 sacks cement in thru drill pipe

Next Plug: @ 330' w/40 " " " " "

Next Plug: @ 40' w/10 sacks cement

15 sacks in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton CONSERVATION DIVISION
Wichita, Kansas ss.

Larry Curtis

(Employee of Operator) or ~~(Operator)~~ of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry Curtis

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 30 day of June, 19 86

Dorothy M Hague
Notary Public



Commission Expires: 5-5-90

DRILLER'S WELL LOG

DATE COMMENCED: June 18, 1986
DATE COMPLETED: June 25, 1986

D & D Production, Inc.
LATHROP A-6
Approx. C W/2
Sec. 3, T27S, R12W
Pratt County, Ks.

ELEVATION: 1886 K.B.

0 - 1019' Surface Soil, Shale, Lime
1019 - 3548' Anhydrite, Shale, Lime
3548 - 3734' Shale & Lime
3734 - 3751' Lime & Shale
3751 - 4104' Lime
4104 - 4396' Chert & Lime
4396 - 4418' Shale
4418 - 4500' Chert
4500' RTD

FORMATION DATA

Anhydrite	1019'
Heebner	3548'
Toronto	3562'
Douglas	3588'
Br. Lime	3734'
Lansing K.C.	3751'
Base K.C.	4104'
Mississippi	4225'
Kinderhook	4396'
Viola	4418'
RTD	4500'

Surface Pipe: Set new
8-5/8", 24# pipe @303'
w/210 sacks 60/40 pozmix
2# gel 3# cc.

AFFIDAVIT


STATE OF KANSAS
COUNTY OF BARTON) ss

Larry Curtis of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 30 day of June 1986

Dorothy M. Hague
Notary Public



RECEIVED
STATE CORPORATION COMMISSION

JUL - 1 1986

CONSERVATION DIVISION
Wichita, Kansas