

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21974-00-00

LEASE NAME E. B. Studer

WELL NUMBER B-2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 3 TWP. 27 RGE. 12 (E) or (W)

COUNTY Pratt

Date Well Completed

Plugging Commenced 2/14/90

Plugging Completed 2/20/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Timberline Oil & Gas Corp.

ADDRESS 105 E. 8th Pratt, KS. 67124

PHONE# (316) 779-9476 OPERATORS LICENSE NO. 9232

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4240'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	263	none
				5 1/2	4196	2049'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sanded bottom to 4000', dumped 5 sacks cement. Shot pipe
@ 3858, 3428', 3026', 2460', 2421', 2218', 2054'.

Plugged with 4-hulls, 10-gel, 50 sacks cement, 10-gel, 1-hulls,
8 5/8" plug 100 sacks 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Timberline Oil & Gas Corp.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

MAR 05 1990

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 2 day of March, 19 90

My Commission Expires:

