

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # #6195 EXPIRATION DATE January 6, 1982
 OPERATOR Aegean Petroleum Inc. API NO. 15-121-22,873
 ADDRESS #7 Lewis Drive COUNTY Miami
Paola, Kansas 66071 FIELD Paola - Rantoul
 ** CONTACT PERSON N. L. Cornelius PROD. FORMATION Squirrel
PHONE 913-294-5157
 PURCHASER _____ LEASE Straley
 ADDRESS _____ WELL NO. A-5
 WELL LOCATION E 1/2 of NW 1/4
 DRILLING C & M Drilling 660' Ft. from SNL Line and
 CONTRACTOR ADDRESS Route #5 660' Ft. from WEL Line of
Paola, Kansas 66071 the NW (Qtr.) SEC 8 TWP 17S RGE 22E.

PLUGGING CONTRACTOR ADDRESS _____
 TOTAL DEPTH 750' PBTD _____
 SPUD DATE 5-26-81 DATE COMPLETED 7-6-81
 ELEV: GR _____ DF _____ KB _____
 DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

WELL PLAT

		8	

(Office Use Only)
 KCC _____
 KGS _____
 SWD/REP _____
 PLG. _____

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____
 Amount of surface pipe set and cemented _____ DV Tool Used? _____

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other _____


ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Garry Duckett, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

SUBSCRIBED AND SWORN TO BEFORE ME this 12th day of July, 1983.
 _____ (Name)



MY COMMISSION EXPIRES: 5-13-86
 _____ (NOTARY PUBLIC)

** The person who can be reached by phone regarding any questions concerning this information.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 1 9 1983
 CONSERVATION DIVISION
 Wichita, Kansas

SIDE TWO.

ACO-1 WELL HISTORY

OPERATOR Aegean Petroleum Inc. LEASE Straley A-5

SEC. 8 TWP. 17S RGE. 22E

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 1/4	7		21'			
Pumping	6 1/4	4 1/2		750'	Portland A	100	6% Gel

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			2 Per Foot	3 1/2 Strip Jets 15 Shots	686-693.
Size	Setting depth	Packer set at			
4 1/2	750'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1 Gal. IS-2, 1 Gal. I-1, 1 Gal. D-4 (11bbl.)	686-693
20/40 Sand 1500#, 10/20 Sand 2000#, 8/12 Sand 5000# (100 bbl water)	
100# WG-1, 8# Breaker "F"	
Date of first production 7-9-81	Producing method (flowing, pumping, gas lift, etc.) Pumping
	Gravity

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	Less than one bbl.		80 %	
Disposition of gas (vented, used on lease or sold) Vented			Perforations	686-693

Thickness of Strata	Formation	Total Depth	Remarks
		0	
2	Soil	2	
26	LM	28	
15	Sh	43	
19	LM	62	
24 86	Sh	86	
14	LM	100	
100	Sh	200	
17	LM	221	
12	Sh	233	
3	LM	236	
11	Sh	247	
5	LM	252	
34	Sh	286	
14	LM	300	
15	Sh	315	
29	LM	344	
7	Sh	351	
23	LM	374	
4	Sh	378	
13	LM	391	
109	Sh	500	
7	Sand Sh	507	
9	Sand	516	
15	Sh	531	
5	LIMEY Sh	536	