

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 6724 EXPIRATION DATE 06/30/83

OPERATOR Cinco Exploration Company API NO. 15-063-20,6510000

ADDRESS P.O. Box 3723 COUNTY Gove

Victoria, Texas 77903 FIELD Wildcat

\*\* CONTACT PERSON Melvin Klotzman PROD. FORMATION None

PHONE 1-800-531-3640

PURCHASER LEASE Smith

ADDRESS WELL NO. 1

WELL LOCATION SW NE

DRILLING Slawson Drilling Company, Inc. 1980 Ft. from north Line and

CONTRACTOR 200 Douglas Building 1980 Ft. from east Line of

ADDRESS Wichita, Kansas 67202 the NE (Qtr.) SEC 25 TWP 13 RGE 28W.

PLUGGING Halliburton

CONTRACTOR ADDRESS P. O. Box 405

Ness City, Kansas 67560

TOTAL DEPTH 4650 PBD 4650

SPUD DATE 3/5/83 DATE COMPLETED 3/12/83

ELEV: GR 2651 DF 2654 KB 2657

DRILLED WITH (CABOX) (ROTARY) (KIX) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 303 DV Tool Used? no

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, (Dry) Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

MELVIN KLOTZMAN, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Melvin Klotzman (Name of Person) Consultant

SUBSCRIBED AND SWORN TO BEFORE ME this 1st day of April 1983.

Notary Public Signature

MY COMMISSION EXPIRES: 2/06/85

\*\* The person who can be reached by phone regarding any questions or information.

STATE RECEIVED NOV 4 1983 KANSAS CORPORATION COMMISSION

FIELD LOG SHEET AS REQUIRED:

SEX

Show all important zones of porosity and contents thereof; core intervals, and all drill-stem tests, including depth interval tested, cushion used, time test open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION:

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<b>DRILLERS LOG</b>				
0' to 306'			Anhydrite	2151'
206' to 2153'			Heebner	3856'
2153' to 2184'			Toronto	3881'
2184' to 3396'			Lansing	3899'
3396' to 3588'			Stark Shale	4122'
3588' to 3780'			Base/Kansas City	4174'
3780' to 3895'			Pawnee	4322'
3895' to 4650'			Fort Scott	4376'
			Cherokee	4402'
			Mississippi	4479'
<p>Ran Petro-Log GR Guard Log from 4650' to surface                      No Drill-Stem Tests.</p>				

Report of all strings set — surface, intermediate, production, etc. **CASING RECORD Used**

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surf. Casing	12 1/4"	8-5/8"	24	303	Halliburton	225	60/40 Poz 2% gel 3%

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Pecker out of

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF
	Water %	Gas-oil ratio bbls. / MCF
Disposition of gas (vented, used on lease or sold)		Perforations

15-023-20651-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Gove SEC. 25 TWP. 13 RGE. 28 E/W  
 Location as in quarters or footage from lines:

		①	
		25	

SW NE  
 Lease Owner Cinco Exploration Company  
 Lease Name Smith Well No. 1  
 Office Address P. O. Box 3723, Victoria, Texas 77903  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed 3/12/83  
 Application for plugging filed 3/12/83  
 Plugging commenced 3/12/83  
 Plugging completed 3/12/83 3:45 a.m.  
 Reason for abandonment of well or producing formation Dry Hole

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marian Schmidt

Producing formation NONE Depth to top          bottom          T.D. 4650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Sand & Shale	Fresh Water	0	200	8 5/8"	303	0
No oil or gas formations.						

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from          feet  
 to          feet for each plug set.

- 1st plug @ 2163' with 20 sks. 50/50 Poz. 6% gel, 3% CC
- 2nd plug @ 1202' with 100 sacks 50/50 Poz. 6% gel, 3% CC
- 3rd plug @ 353' with 40 sacks 50/50 Poz. 6% gel, 3% CC
- Top plug @ 40' with 10 sacks 50/50 Poz. 6% gel, 3% CC
- 10 sacks in rat hole
- Job complete @ 3:45 a.m. 3/12/83

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

STATE OF TEXAS COUNTY OF VICTORIA, ss.

MELVIN KLOTZMAN (employee of owner) ~~XXXXXXXXXXXXXXXXXXXX~~ of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) [Signature]

P. O. Box 3723 - Victoria, TX 77903  
 (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of April, 19 83

[Signature]  
 Notary Public.

My Commission expires: 2/06/85

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 4 1983  
 CONSERVATION DIVISION  
 Wichita, Kansas