

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil Gas, Dry, SWD, OWWO, Injection. Type and complete **ALL** sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Reif Oil Operations Inc.

API NO. 15-009-22,783-00-00

ADDRESS Box 298

COUNTY Barton

Hoisington, Kansas 67544

FIELD _____

**CONTACT PERSON Stanley C. Lingreen

PROD. FORMATION _____

PHONE 913-483-5355

LEASE Butler

PURCHASER Conoco Inc.

WELL NO. #2

ADDRESS Box 264

WELL LOCATION C OF N 1/2 of SW SW

Lyons, KS

DRILLING Revlin Drlg., Inc.

330 Ft. from North Line and

CONTRACTOR

660' Ft. from West Line of

ADDRESS Box 293

the SEC. 33 TWP. 17 RGE. 13

Russell, Kansas 67665

WELL PLAT

PLUGGING

CONTRACTOR

ADDRESS _____



KCC _____
KGS _____
(Office Use)

TOTAL DEPTH 3380' PBTD _____

SPUD DATE 5-10-82 DATE COMPLETED 5-16-82

ELEV: GR _____ DF _____ KB 1865'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented set @ 773' w/ DV Tool Used? _____

50-50 Poz Mix 2% Gel 3% CC

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton SS, I, _____

Donald J. Reif OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS President ~~XXXXX~~ (FOR) (OF) Reif Oil Operations, Inc.

OPERATOR OF THE Butler LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 2 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 15th DAY OF June, 19 82, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

Reif Oil Operations, Inc.
Donald J. Reif, President

(S) _____

SUBSCRIBED AND SWORN BEFORE ME THIS _____ DAY OF _____, 19 _____.

NOTARY PUBLIC

MY COMMISSION EXPIRES: _____

**The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

RECEIVED
STATE CORPORATION COMMISSION
7 1983
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale & Sand	00	660		
Shale	660	770		
Anhydrite	770	776		
Shale	776	1515		
Fort Riley	1515	1740		
Shale	1740	2065		
Shale w/ Lime	2065	2904		
Lime	2904	3047		
Shale & Lime	3047	3160		
Lime	3160	3215		
Shale w/ Lime	3215	3330		
Lime	3330	3380'	R.T.D.	

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used) ~~XXXXXX~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	22#	773'	50-50 Poz Mix	325	2% Gel 3% CC
Production	7 7/8	5 1/2	15#	3379	50-50 Poz Mix	150	18% Salt
							40bbls salt flush

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Pecker set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production
6-15-82Producing method (flowing, pumping, gas lift, etc.)
pumping

Gravity 38.0

RATE OF PRODUCTION PER 24 HOURS	Oil 12 bbls.	Gas MCF	Water % bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)			Perforations	