

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-21,841-ΔΔ-ΔΔ

LEASE NAME Sitton

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

2310 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 26 TWP. 27 RGE. 11 (X) or (W)

COUNTY Pratt

LEASE OPERATOR Deutsch oil Company

ADDRESS 107 North Market, Suite 1008 Wichita, KS 67202

PHONE#(316) 267-7551 OPERATORS LICENSE NO. 3180

Date Well Completed 6-23-87

Character of Well D&A

Plugging Commenced 6-23-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-23-87

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City
 to be filed by _____

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
from bottom to 4090' w/80 sacks cement thru drill pipe

Next Plug: @ 560' w/50 sacks cement thru drill pipe

Next Plug: @ 330' w/50

Top Plug: @ 40' w/10 sacks cement 10 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson


(Address) P.O. Box 823 Great Bend, KS 67530

RECEIVED
 STATE CORPORATION COMMISSION

STATE SUBSCRIBED AND SWORN TO before me this 24 day of June, 19 87

JUN 26 1987

My Commission Expires:
 CONSERVATION DIVISION
 Wichita, Kansas



DRILLER'S WELL LOG

DATE COMMENCED: June 15, 1987
DATE COMPLETED: June 23, 1987

Deutsch Oil Company
SITTON #1
N/2 NE SW
Sec. 26, T27S, R11W
Pratt County, Ks.

ELEVATION: 1701 K.B.

0	-	541	Surface Soil, Red Bed
541	-	560	Anhydrite
560	-	2963	Lime & Shale
2963	-	3333	Lime
3333	-	3365	Shale & Lime
3365	-	3521	Shale
3521	-	3546	Lime & shale
3546	-	3914	Lime
3914	-	3989	Shale, Lime, Chert, Sand
3989	-	4087	Chert & Lime
4087	-	4252	Shale
4252	-	4352	Chert
4352	-	4400	Shale & Sand
		4400	RTD

FORMATION DATA

Anhydrite	541
Topeka	2963
Heebnar	3333
Toronto	3340
Douglas	3365
Br. Lime	3521
Kansas City	3546
Base K.C.	3914
Conglomerate	3937
Mississippi	3989
Kindershook	4087
Viola	4252
Simpson Sh.	4352
Simpson Sd.	4360
RTD	4400

Surface Pipe: Set now
3-5/8" 20# pipe @ 300
w/200 sacks 60/40 pozmix
2% gel 3% cc


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 24 day of June 1987.



Dorothy M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1987

CUNLEY, HOLLANDSON
Wichita, Kansas