

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

15-051-01347-00-00

COUNTY Ellis SEC 16 TWP 15 RGE 18W E/W
Location as in quarters or footage from lines:

SW NE SWSE

Locate Well
correctly on above
Section Platt.

Lease Owner Kelso Casing Pulling
Lease Name Ohnmacht #1 Well No.
Office Address P.O. Box 347 Chase, Kansas 67524
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed
Application for plugging filed
Plugging commenced 10-28-82
Plugging completed 11-2-82
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation Depth to top bottom T.D. 3602'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1198'	none
				5-1/2"	3598'	3059'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from feet
to feet for each plug set.

Plugged off bottom with 5 sacks cement, sand to 3600' and 5 sacks cement. Shot casing @3055', pulled a total of 94 joints of 5-1/2" casing. Plugged well with 25 sacks cement, 4 sacks hulls, 15 sacks gel, 70 sacks cement, 5 sacks gel, 1 sack hulls, 8-5/8" plug and 70 sacks cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF KANSAS COUNTY OF RICE, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November, 19 82

My Commission expires:




Irene Hoover RECEIVED
Notary Public.
COMMISSION

NOV 08 1982
11-8-82
CONSERVATION DIVISION
Wichita, Kansas

15-051-01347-00-00

COPY

WELL LOG BUREAU-KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, KansasCompany- TOMLINSON & KATHOL
Form- Ohrmacht No. 1SEC. 16 T. 15 R. 18W
SW NE SWSETotal Depth. 3602'
Comm. 12-6-56 Comp. 12-20-56
Shot or Treated.
Contractor. Mallonee Drlg. Co., Inc.
Issued. 3-16-57County Ellis
KANSASCASING:
8 5/8" 1198' w/500 sx cem.
5 1/2" 3598' w/75 sx cem.

Elevation. 2025' KB

Production. 25 BOPD

Figures indicate Bottom of Formations.

shale-sand	215
shale-shells	465
Iron pyrites	469
shale-shells	500
shale-sand-shells	575
sand	815
shale-shells	860
shale	915
shale-lime-shells	1090
shale-shells-red bed	1183
Anhydrite	1220
shale-shells	1625
shale-shells-salt	1855
shale-lime	2735
shale-shells	2765
lime-shale	2960
shale	3007
lime-shale	3130
lime	3205
lime-shale	3255
lime	3549
lime-shale	3602
Total Depth	

TOPS:

Anhydrite(socout)	1183
Heebner	3265
Toronto	3284
Lensing	3309
B/Kansas City	3527
Arbuckle	3596

DST #1 3327-3339 Open 1 hr.,
SI 20 mins., rec. 150' salt
wtr. IFP 0#. FFP 80#. BHP 820#.DST #2 3588-3602 Open 1 hr.,
SI 20 mins., strong blcs
throughout test, rec. 300' oil.
IFP 80#, FFP 160#, BHP 860#,
HP 2120#.

K. G. S. LIBRARY

OHNMACHT #1

SW NE SE 16-15-18

ELLIS Co. KS

Darrell

NO RECORD on weight
of 5 1/2 csg. assume
it is 14 # as well
was originally a
producer.

8 7/8 @ 1198'
CIRC

no perfor

open hole 3645-3685

Darrell

Have called Wichita &
they will send out a Driller
Log.

Stanley

5 1/2 @ 3598'
?

4 1/2 LINES from
3585-3645'
Cemented

1 H. 2 1/2" 8 R C O E
Cement lined
tubing in lines

open hole
3645 to 3685 ft

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1983

CONSERVATION DIVISION
Wichita, Kansas