

15-151-10564-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 12 Twp. 26 Rge. (E) 12 (W)
Location as "NE/CNW&SW" or footage from lines. C NE SE NE

Lease Owner D. R. Lauck Oil Company, Inc.

Lease Name Claycomb Well No. 1

Office Address 301 So. Broadway Wichita 2 Kans

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed July 24 19 43

Application for plugging filed June 25 19 52

Application for plugging approved June 25 19 52

Plugging commenced Sept. 9 19 52

Plugging completed Sept. 21 19 52

Reason for abandonment of well or producing formation production depleted

If a producing well is abandoned, date of last production Sept. 1 19 52

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation Viola Depth to top 4122 Bottom 4138 Total Depth of Well 4142 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing	dry	3609	3967			
Miss. Lime	dry	3967	4122			
Viola	oil	4122	4142			
				10 3/4"	300'	none
				5 1/8"	4131	3154

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4142'	to	4120	sand			
4120	to	4095	cement 5 sx			
4095	to	250	mud			
250	to	235	rock bridge			
235	to	200	cement 20 sax			
200	to	20	mud			
20	to	cellar	cement 10 sx			

RECEIVED
STATE CORPORATION COMMISSION
OCT - 7 1952
10-7-52
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor R & S Pipe Pulling Co.
Address Ellinwood Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
P. R. Bishop (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) P. R. Bishop
Wichita Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of October 19 52

My commission expires Sept. 14, 1955
Elizabeth Gay Notary Public

24-2675-9 2-52-20M

PLUGGING
SEC 12 Twp 26 R 12
BOOK PAGE 26 LINE 6

15-151-10564-0000

CLAYCOMB No.1

NE SE NE 12-26-12
Pratt County, Kans

LAUCK & MONCRIEF

Contractor: Hinkle Oil Co.

CASING RECORD:

300' 10"
4131' 5"

Commenced June 21, 1943

Completed July 15, 1943

0	190	sand and clay
190	691	red rock
691	1410	shale & shells
1410	1618	shale
1618	1913	lime
1913	1995	broken lime
1995	2258	lime
2258	2334	broken lime
2334	2344	shale
2344	2652	broken lime
2652	2756	shale
2756	2834	shale and lime
2834	2995	broken lime
2995	3075	shale
3075	3128	shale & lime
3128	3141	lime
3141	3301	broken lime
3301	3520	lime
3520	3580	shale
3580	3639	broken lime
3639	3688	lime
3688	3720	lime and chert
3720	3750	broken lime
3750	3940	lime
3940	3982	lime and chert
3982	3992	lime
3992	4 008	chat
4008	4016	lime and chat
4016	4054	shale and lime
4054	4071	lime
4071	4125	shale
4125	4138	lime
4138	total depth	rotary
	4141	lime
		plug back

Tops: Derrick floor

Lansing:	3609
Miss.	3967
Viola	4122
Pay	4130

Temporary productivity: July 24, 1943
Permanent productivity: Dec. 18, 1943

77 bbls
68 "

