

15-151-10561-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 12 Twp. 26S Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines NE/4 SW/4 SE/4

Lease Owner Monsanto Chemical Company

Lease Name Ford

Well No. 4

Office Address P. O. Box 580, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed October 6, 19 43

Application for plugging filed February 28, 19 56

Application for plugging approved February 29, 19 56

Plugging commenced March 25, 19 56

Plugging completed March 26, 19 56

Reason for abandonment of well or producing formation Insufficient production

If a producing well is abandoned, date of last production November 19 55

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Viola Depth to top 4149 Bottom Total Depth of Well 4154 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	310'	None
				5 1/2"	4152'	2011'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged with sand from 4154' to 4140' with 5 sacks of ~~port~~ cement on top of sand. Shot pipe off at 2011' and pulled 6 joints. Circulated heavy mud. Finished pulling casing and plugged with heavy mud to 300'. Set rock plug @ 300' with 20 sacks of cement on top of plug. Heavy mud to 35' and set rock plug @ 35' with 10 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF KANSAS, COUNTY OF PRATT, ss.

J. B. Gibbs (employee of owner) or (~~owner~~ / ~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P. O. Box 580, Pratt, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of March, 19 56

My commission expires September 19, 1959

Notary Public.

PLUGGING
FILE SEC 12 T 26 R 12W
BOOK PAGE 42 LINE 12

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1956
3-29-56
CONSERVATION DIVISION
Wichita


15-151-10561-0000

LION OIL REFG. CO.
Viola Ford No. 4.

SEC. 12 T. 26 R. 12 W
NE SW SE

Total Depth. 4154 Corr.
Comm. 8-27-43 Comp. 9-23-43
Shot or Treated.
Contractor. R.W. Rine Drlg. Co.
Issued. 10-23-43

County. Pratt



CASING:
8 5/8" 310' Cem.
6 1/2" 4154' Corr. Cem.

Elevation.

Production. Pot. 55 BO 6 Hrs

Figures Indicate Bottom of Formations.

clay, sand, red bed	top-300
red bed	310
red bed & shale	450
red bed & shell	1090
shale & lime	1385
shale & lime shells	1695
lime & shale	1840
lime brkn	1940
shale & shells	2095
lime & shale	2195
shale & lime strk	2285
lime & shale	2395
shale & lime shells	2510
shale	2750
shale & shell	2860
shale & lime	2980
shale	3085
shale & lime	3220
lime	3400
shale & lime	3460
lime	3580
shale & lime	3695
lime	3745
lime & shale	3805
lime	3965
lime & chert	4019
shale w/lime strks	4036
chert & shale	4047
shale	4084
shale & lime	4145
shale	4153
chert & lime	4158
4158 equals 4154 Corr.	
Total Depth.	

Top Viola 4149 Corr.

PLUGGING
 FILE SEC 12 T 26 R 12W
 BOOK PAGE 42 LINE 12

RECEIVED
 STATE CONSERVATION COMMISSION
 MAR 1 - 1956
 3-1-56
 CONSERVATION DIVISION
 Wichita, Kansas