

15-151-10575-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Pratt County, Sec. 13 Twp. 26 Rge. (E) 12 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NW NE  
Lease Owner Sohio Petroleum Company  
Lease Name Haley Well No. 2  
Office Address Box 673, Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 12-9 19 43  
Application for plugging filed 10-9 19 51  
Application for plugging approved 10-11 19 51  
Plugging commenced 11-5 19 51  
Plugging completed 11-5 19 51  
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production March 19 51  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Great Bend, Kansas  
Producing formation Viola Depth to top 4146' Bottom 4155' Total Depth of Well 41 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Viola	Oil	4146'	4155'	7"	4152'	2556'
				10"	298'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded to 290'. Set plug at 290' - 25 sacks cement on plug, mudded to 25' and filled to bottom of cellar with 10 sacks cement.

Name of Plugging Contractor Carrol Brothers Casing Pulling Company  
Address Great Bend, Kansas



STATE OF KANSAS, COUNTY OF RUSSELL  
D. W. Smith (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. W. Smith

SUBSCRIBED AND SWORN TO before me this 8 day of November, 19 51

(Address) Russell Miller  
Notary Public.

My commission expires July 2, 1953

23-8390-s 6-51-20M

PLUGGING  
FILE SEC 13 Twp 26 R 12 W  
BOOK PAGE 115 LINE 36

COPY

Haley #2  
NE/4 NW/4 NE/4 Section 13-26S-12W  
Pratt County, Kansas  
Margay Oil Corporation

Commenced: September 29, 1943  
Completed: December 9, 1943

Surface clay and sand	0	200	Lime and shale	3517	3563
Red bed	200	298	Shale	3563	3607
Red bed, shale, shells	298	720	Shale and lime	3607	3637
Shale and shells	720	1120	Lime, sandy	3637	3647
Shale, lime shells, salt	1120	1420	Lime	3647	3682
Salt, shale, shells	1420	1540	Lime, hard	3682	3703
Shale and shells	1540	1640	Lime	3703	3788
Lime, cherty	1640	1685	Lime and shale	3788	3812
Lime and shale	1685	1775	Lime	3812	3995
Lime	1775	1959	Chert and lime	3995	4017
Lime, shale streaks	1959	2040	Cherty lime	4017	4030
Shale and shells	2040	2100	Chert	4030	4039
Broken lime and shale	2100	2195	Lime and shale	4039	4059
Stickey shale	2195	2215	Lime, shale streaks,		
Shale	2215	2230	cherty	4059	4075
Lime	2230	2250	Lime and shale, broken	4075	4093
Shale and shells	2250	2275	Shale	4093	4105
Lime broken	2275	2280	Lime and shale	4105	4116
Shale and shells	2280	2440	Shale	4116	4136
Lime	2440	2455	Shale and lime	4136	4151
Shale	2455	2495	Viola lime, cherty	4151	4155
Shale and shells	2495	2585			
Shale	2585	2600	TOTAL DEPTH	4155	
Lime	2600	2640			
Shale, lime shells	2640	2720			
Shale and shells	2720	2816			
Shale	2816	2825			
Lime	2825	2845			
Lime, shale streaks	2845	2895			
Shale and shells	2895	2910			
Lime	2910	2936			
Lime, shale, shells	2936	3075			
Lime, broken	3075	3104			
WHIPSTOCKING					
Lime, hard	3104	3112			
Lime	3112	3180			
Lime and shale streaks	3180	3200			
Lime, broken	3200	3255			
Lime	3255	3283			
Lime and shale	3283	3327			
Lime	3327	3375			
Sand	3375	3395			
Lime	3395	3448			
Lime and shale	3448	3481			
Broken lime and shale	3481	3517			

Casing Record:

10-3/4" casing set at 298' and cemented with 250 sacks cement

7" casing set at 4152' and cemented with 150 sacks cement

FILED  
STATE OF OKLAHOMA  
OCT 11 1951  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF OKLAHOMA)  
COUNTY OF TULSA ) ss

I hereby affirm that the above and foregoing is a true and correct copy of the log of your Haley Well #2, located in the Northeast Quarter of the Northwest Quarter of the Northeast Quarter of Section 13, Township 26 South, Range 12 West, Pratt County, Kansas

PLUGGING

FILE SEC 13: 26R 13W  
BOOK PAGE 115 LINES 36

Helmerich & Payne, Inc.

By: /s/ William Brookhurst  
Treasurer

Subscribed and sworn to before me, a Notary Public, this 21st day of December, 1943.

/s/ Sue Griffin  
Notary Public

My commission expires July 22, 1947.