


15-151-00200-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail of Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County, Sec. 13 Twp. 26S Rge. 12E (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SE SE SW
Lease Owner BAY PETROLEUM CORPORATION
Lease Name SCHWERTFEGER Well No. 1
Office Address 1651 Grant Street, Denver, Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10/16 19 50
Application for plugging filed 10/15 19 50
Application for plugging approved 10/15 19 50
Plugging commenced 10/15 19 50
Plugging completed 10/16 19 50
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. STONE
Producing formation Depth to top Bottom Total Depth of Well 4350 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	358'	None

Describe in detail the manner in which the well was plugged; indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 350', set plug and cemented with 20 sacks cement and mud hole to 30', set plug and cemented with 10 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
10-25-50
OCT 25 1950
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Bay Petroleum Corporation
Address Box 513, Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Glen E. Armour (employee of owner) or (owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God
(Signature) Glen E. Armour

(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of October, 1950

May, 20, 1954

My commission expires

22-7377-s 4-49-10M

PLUGGING
FILE SEC 13 T 26 R 12E
BOOK PAGE 35 LINE 43

Notary Public.

COMPANY: BAY PETROLEUM COMPANY Rotary Drilling Commenced: 9-29-50
 Denver, Colorado Rotary Drilling Completed: 10-16-50

LOCATION: SWERTFEGER #1, SE SE SW
 Sec. 13-26S-12W
 Pratt County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY, INC.
 Wichita, Kansas

CASING RECORD: 358' (16 Jts.) 8 5/8" surface casing set at 358' in a 12 1/4" hole, cemented with 200 sacks cement.

Drilled 7 7/8" hole from 358' to 4350' T.D. No oil string run.

LOG

(Figures indicate bottom formation - measurements from top rotary bushing.)

Cellar	5	Circulate for samples at 3707'.
Sand	165	" " " " 3714'.
Red Bed	880	" " " " 3747'.
Shale & Salt	1590	" " " " 3772'.
Shale & Shells	1750	" " " " 3820'.
Shale & Lime	1950	" " " " 3850'.
Lime	2045	" " " " 3890'.
Lime & Shale	2210	" " " " 4129'.
Lime	2325	" " " " 4139'.
Lime & Shale	2840	" " " " 4144'.
Lime	2925	" " " " 4149'.
Lime & Shale	3075	" " " " 4158'.
Lime	3330	" " " " 4166'.
Lime & Shale	3405	" " " " 4175'.
Lime	3409	" " " " 4240'.
Lime & Shale	3605	" " " " 4260'.
Lime	4010	" " " " 4290'.
Lime & Chert	4034	" " " " 4301'.
Lime	4057	" " " " 4312'.
Lime & Shale	4077	" " " " 4330'.
Lime	4290	" " " " 4350'.
Lime & Shale	4312	
Lime	4350 Rotary T.D.	Filled hole with heavy mud from 4350' to 350'. Spotted 20 sacks cement and mudded to 30'. Filled with 10 sacks cement to bottom of cellar.

Slope test at 500' - 0° off.
 Slope test at 1000' - 0° off.
 Slope test at 1500' - 0° off.
 S.L.M. at 1500' - O.K.
 Slope test at 2000' - 0° off.
 Slope test at 2500' - 0° off.
 S.L.M. at 3000' - O.K.
 S.L.M. at 3500' - O.K.
 Slope test at 4000' - 0° off.
 S.L.M. at 4350' - O.K.

RECEIVED
 STATE CORPORATION COMMISSION
 16-25-50
 OCT 25 1950
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, G. W. Sebitts, Secretary of PICKRELL DRILLING COMPANY, INC., hereby certifies in behalf of said corporation, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY, INC.

By G. W. Sebitts
 Secretary

PLUGGING
 STATE OF KANSAS) FILE SEC. 13-T 26 R 120
 COUNTY OF SEDGWICK) LOCK PAGE 35 LINE 43

BE IT REMEMBERED that on this 20th day of October, 1950, before me, the undersigned, a Notary Public, duly commissioned, in and for the county and state aforesaid, came G. W. Sebitts, Secretary of Pickrell Drilling Company, Inc., a corporation of the State of Kansas, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said corporation, and he duly acknowledged the execution of the same for himself and for said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My commission expires Jan. 1953

Etha Zimmerman
 Notary Public