

15-151-10574-00-4


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Pratt County, Sec. 13 Twp. 26 Rge. 12W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE  
Lease Owner Sohio Petroleum Company  
Lease Name Haley Well No. 1  
Office Address Box 673, Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed Recompleted 4-30 19 51  
Application for plugging filed 10-9 19 51  
Application for plugging approved 10-11 19 51  
Plugging commenced 10-30 19 51  
Plugging completed 10-30 19 51  
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production March 19 51  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Great Bend, Kansas  
Producing formation Viola Depth to top 4155' Bottom 4160' Total Depth of Well 4336 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Viola	Oil	4155'	4160'	5 $\frac{1}{2}$ "	4156'	2030'
				10"	300'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

4336 - 4145 Rock  
4145 Dumped 5 sacks cement  
4145 - 300 Mud  
300 Bridged off and dumped 20 sacks cement  
25' Mud, and capped with 10 sacks cement  
to base of cellar

Name of Plugging Contractor Carrol Brothers Casing Pulling Co.  
Address Great Bend, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
NOV-9-51  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
D. W. Smith (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D.W. Smith

(Address)

SUBSCRIBED AND SWORN TO before me this 8 day of November, 1951

My Commission Expires July 2, 1953

My commission expires

Russell Miller  
Notary Public.

23-8390-s 6-51-20M

PLUGGING  
FILE SEC 13 T 26 R 26  
BOOK PAGE 115 LINE 35

15-151-10574-00-01

COPY

Casing Record:  
300' 10"  
4156' 5"

HALEY NO. 1 NEc 13-26-12 Pratt County, Kansas.  
Margay Oil Company  
Contractor Hinkle Oil Company  
Commenced July 26, 1943 Completed August 21, 1943.

0	175	Sand and Shale	
175	645	Red Rock	
645	1120	Shale and Shells	
1120	1340	Salt	
1340	1650	Shale and Shells	
1650	1998	Lime	
1998	2050	Broken Lime	
2050	2088	Shale	
2088	2259	Lime	
2259	2515	Lime and Shale	
2515	2656	Lime	
2656	2722	Lime and Shale	
2722	2765	Lime	
2765	2795	Shale	
2795	2827	Lime	
2827	3021	Broken Lime and Shale	
3021	3189	Lime	
3189	3271	Broken Lime	
3271	3487	Lime	
3487	3527	Sandy Shale	
3527	3555	Lime	
3555	3606	Shale	Top K.C. Lime 3606
3606	3942	Lime	
3942	4021	Chert	
4021	4036	Shale	
4036	4052	Chert and Shale	
4052	4132	Shale	
4132	4154	Shale	Top Viola Lime 4154
4154	4160	Viola Lime	
4160	T.D.		

Drilled with Cable tools from 4156 to 4160.  
Hole filled to top with oil. Made one flow.  
1 Hr. and 15 minutes later well flowed approximately 25 bbls.  
Then was shut in.

State of Kansas )  
                  ) ss  
County of Sedgwick)

STATE OF KANSAS  
OCT 11 1943  
18-11-51

I hereby certify that the above is a true and correct log as compiled from the drilling reports kept at said well.

/s/ J. B. Hinkle

Subscribed to and sworn to before me this 1st day of September, 1943.

/s/ Muriel A. Upton  
Notary Public

My commission expires 1-17-46.

**PLUGGING**  
FILE SEC 13 T X6 R 130  
BOOK PAGE 15 LINE 35