


15-151-00354-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Pratt County. Sec. 17 Twp. 26 Rge. 12 (E) 12 (W)  
Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner Musgrove Petroleum Corporation  
Lease Name TRIMPE Well No. 1  
Office Address 518 Petroleum Building, Wichita, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 31, 19 54  
Application for plugging filed May 31, - verbally 19 54  
Application for plugging approved May 31, - verbally, 6-1-54 19 54 written  
Plugging commenced May 31, 19 54  
Plugging completed May 31, 19 54  
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - verbally

Name of Conservation Agent who supervised plugging of this well Warren H. Horner, Box 207, Great Bend, Ks.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 444 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	290'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud to 280'.  
Set first plug with 20 sacks cement through drill pipe.  
Filled hole with mud to 35'.  
Set second plug with 1/3 sack hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Musgrove Petroleum Corporation  
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas COUNTY OF Sedgwick  
I, Gordon L. Koelling, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Gordon L. Koelling  
518 Petroleum Building, Wichita, Kansas. (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 19 54  
My commission expires September 24, 1956.  
Thomas L. Stinson Notary Public.

**PLUGGING**  
FILE SEC 17 T 26 R 12W  
BOOK PAGE 32 LINE 24

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 4 - 1954  
6-4-54  
CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPENY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	Trimpe #1
LOCATION:	SW SW SW, Sec. 17-26-12W Pratt County, Kansas
COMMENCED:	May 14, 1954
COMPLETED:	May 31, 1954

0	100	Surface soil & clay
100	130	Sand & clay
130	260	Sand
260	430	Red Bed
430	750	Red bed & sand
750	775	Anhydrite
775	935	Shale, red bed & sand
935	970	Shale & red bed
970	1635	Shale & shells
1635	1725	Shale & lime shells
1725	2655	Lime & shale
2655	2850	Shale & shells
2850	3120	Shale & lime
3120	3350	Lime
3350	3460	Lime & shale
3460	3630	Lime
3630	3705	Lime & shale
3705	3800	Lime
3800	3854	Lime & shale
3854	3945	Lime
3945	3981	Lime & shale
3981	4053	Lime
4053	4137	Lime & shale
4137	4213	Lime & chert
4213	4232	Lime (Mississippi)
4232	4254	Lime (Viola)
4254	4302	Chert & lime
4302	4320	Lime
4320	4325	Simpson
4325	4412	Lime, sand & shale
4412	4444	Arbuckle lime
	4444	Rotary Total Depth

Set 8-5/8" surface pipe at 290' with 175 sacks of cement & 2 calcium chloride  
Dry and Abandoned

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the TRIMPE #1, SW SW SW, Section 17-26-12W, Pratt County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

**PLUGGING**  
WELL SEC 12-26-12W  
BOOK PAGE 37 LINE 34

MUSGROVE PETROLEUM CORPORATION

BY *Gordon L. Koelling*  
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 3rd day of June, 1954.

*Gordon L. Koelling*  
Notary Public

My commission expires September 24, 1956.

JUN 4 - 1954  
6-4-54  
CONSERVATION DIVISION  
Wichita, Kansas