

15-151-00387-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 17 Twp. 26S Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner White Eagle Oil Co.

Lease Name McKibbin Well No. 1

Office Address 1st National Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-29 19 53

Application for plugging filed 9-29 19 53

Application for plugging approved 10-2 19 53

Plugging commenced 10-2 19 53

Plugging completed 10-2 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives Pratt, Kansas

Producing formation None Depth to top - Bottom - Total Depth of Well - Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner Shale		3478	3485	8-5/8	622	None
Toronto Lime		3497	3499			
Lansing-K.C.	Water	3679	4065			
Viola	Water	4182	4200			
Arbuckle Dolo.	Water	4361	-			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from - feet to - feet for each plug set.

Hole left full of 10# mud. 20 Sack cement plug from 300' up to 40' - Filled hole from 40' to bottom of cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ben F. Brack

Address Wichita, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss. M. J. Heald Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. J. Heald Jr.
1st National Bldg., Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of October, 19 53

Dagmar Waldrop
Notary Public.

My commission expires 8-19-57

PLUGGING
FILE SEC-7 T-26 R-12W
PAGE 133 LINE 13

RECEIVED
STATE CORPORATION COMMISSION
OCT-7-1953
10-7-53
CONSERVATION DIVISION
Wichita, Kansas

15-151-00387-0000

BEN F. BRACK OIL COMPANY, INC.
309-10 BROWN BUILDING
WICHITA 2, KANSAS

McKIBBIN #1

NE NE NE

Sec. 17-26S-12W
Pratt County, Kansas
Commenced: 9-5-53
Completed: 9-29-53

TOTAL DEPTH: 4412'
ELEVATION: 1892' D.F.

WELL LOG

Sand	0 -	50"
Sand & Shells		180
Shale & Shells		340
Blue Shale		400
Red Bed		540
Sand		570
Red Bed		705
Shale & Shells		848
Anhydrite		880
Shale & Shells		1410
Salt		1530
Shale & Lime		1975
Lime		2055
Lime & Shale		2190
Lime		2380
Lime & Shale		2530
Shale & Lime		2675
Shale		2725
Shale & Shells		2910
Shale & Lime		2935
Lime		3015
Lime & Shale		3150
Shale & Lime		3265
Lime		3954
Lime & Chert		3977
Lime W/Chert Streaks		4005
Lime Iron		4025
Lime		4154
Lime W/Chert		4161
Lime & Chert		4241
Cherty Lime		4259
Lime & Shale		4283
Lime		4311
Lime & Sand		4335
Lime		4370
Arbuckle Lime		4391
Lime		4412

T.D. D. & A.

CASING

RECEIVED
STATE COMMISSION

8 5/8"

622'

001-7-353
10-7-53
CONSERVATION DIVISION
Wichita, Kansas

To the best of my knowledge, the above is a true and correct statement of the depths and formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By Clarence Brack

PLUGGING
FILE SEC 17 T 26 R 12W
BOOK PAGE 133 LINE 13

WITNESSED:

Estelle Crest

October 1, 1953.