


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pratt County, Sec. 28 Twp. 26 Rge. 12W (E) (W)
Location as "NE/CNW&SW" or footage from lines C-NE-SW
Lease Owner Wayne L. Kirkman, Oil and Gas Operations
Lease Name Briggeman Well No. # 2
Office Address Box 18148, Wichita, Kansas 67201
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 19 75
Application for plugging filed July 3 19 75
Application for plugging approved July 3 19 75
Plugging commenced July 3 19 75
Plugging completed July 7 19 75
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Russ Biberstien
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3205
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	302'	none
				5 1/2	2120'	1667'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

(BOTTOM HOLE PLUG)---Sand from total depth to 1900' and dump 5 sacks of cement.

(TOP HOLE PLUG)---Mix 2 hulls and 10 gell release plug and pump 100 sacks of 50/50 pos mix 2% gell into surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dunbar Drilling Inc.
Address 5252 N. Broadway Wichita, Kansas 67219

STATE OF Kansas COUNTY OF Sedgwick ss.
W. P. Simmons (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. P. Simmons
5252 N. Broadway Wichita, Kansas 67219
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of July 19 75

My commission expires Nov. 19, 1977

Frances J. Simmons
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
7-29-75
JUL 29 1975
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

BRIGGEMAN #2

CASING RECORD:
8 5/8" set at 302'
w/285 sacks cement

OPERATOR: Wayne L. Kirkman

DESCRIPTION

CONTRACTOR: Search Drilling Co.

C NE SW,
Sec. 28-26S-12W
Pratt County,
Kansas

TOTAL DEPTH

COMMENCED: May 7, 1975

3205'

COMPLETED: May 14, 1975

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface, soil and clay	0	40
Sand	40	235
Redbed Shale	235	312
Redbed Shale	312	504
Shale	504	779
Anhydrite	779	790
Shale and Salt	790	1530
Shale	1530	1700
Lime and Shale	1700	1941
Lime and Shale	1941	1963
Lime and Shale	1963	1980
Lime and Shale	1980	2220
Lime and Shale	2220	2431
Lime and Shale	2431	2591
Shale and Sand	2591	2715
Lime and Shale	2715	2793
Lime and Shale	2793	2960
Lime and Shale	2960	3088
Lime and Shale	3088	3120
Lime, Shale, Sand	3120	3133
Lime	3133	3143
Lime	3143	3148
Lime	3148	3153
Lime and Shale	3153	3205

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1975
7-3-75
CONSE

Run 73 joints used
5 1/2" casing set at
2120', cemented with
75 sack common, 10%
salt plug down at 4:00 PM
by Sun Oil Well Cementing.

I certify that this is a true and correct copy of the above log to the best of my knowledge and belief.

SEARCH DRILLING COMPANY

M. A. Drexler
M. A. Drexler

Subscribed and sworn to before me this 16th. day of May, 1975

My Commission expires:
August 5, 1975

Virginia S. Fabian
Virginia S. Fabian Notary Public

