

State of Kansas



FORM - CP-2  
Rev. 6-26-62

15-007-30238-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 18 1966  
04-18-1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Curley Brau of Edmiston Drilling Co., Inc has this date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 425 1st National Bank Bldg., Wichita, Kansas

Lease Name: McDaniel Well No. # 1

Location: C NW SE Sec. 2 Twp. 32 Rge. 10 (E) (W) W

County Barber Total Depth 4435' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Brau was instructed to plug the well as follows:

225' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fill hole with drilling mud to 220', 1st cementing plug, bridge with 1/4 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,  
*Archie Elving*