



GEORGE DOCKING Governor  
 MARION BEATTY Chairman  
 HARRY G. WILES Commissioner  
 RICHARD C. BYRD Commissioner  
 RAYMOND B. HARVEY Secretary  
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS  
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

I have this date January 31, 1959, 19    , authorized the following plugging operation:

Operator's Full Name: Rupp Fergudon Oil Co.

Complete Address: 523 Petroleum Bldg., Wichita, Kans.

Lease Name: Long Well No. 1

Location: SW NE SE Sec. 16 Twp. 26 Rge. 12 (E) (W) X

County: Pratt Total Depth: 4150

Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Operator was instructed to plug well as follows:

300' of 8 5/8" surface casin circulated with cement. Fill  
hole to 290' with heavy drilling mud. Set cementing plug with  
four gallon hulls, at 290'. Place 20 sack cement through drill  
pipe on top plug. Heavy drilling mud to 35'. Set cementing plug  
plug from 35' and cement to base of cellar.

Very truly yours,

Signed:   
 Conservation Division Agent