

State of Kansas



15-151-20331-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED ^{New Address}
STATE CORPORATION COMMISSION
Conservation Division
Wichita, Kansas 67202

APR 20 1976

4-20-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Kirkman of W.L. Kirkman Inc has this date requested permission to plug the following described well:

Mr. Kirkman guarantees payment of the plugging fee.

Operator's full Name: W.L. Kirkman Inc

Complete Address: 434 N Market Suite 110 Wichita, KS

Lease Name: Stead Well No. 1

Location: C SW/SW Sec. 22 Twp. 26s Rge. 12 (E)(W) W

County: Pratt Total Depth 1972 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kirkman was instructed to plug the well as follows:

284 ft 8 5/8 surface cemented with 225 sacks. Fill hole

to 250 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to

40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.

2 sacks cement in rat hole.

Very truly yours,

Russell B. ...
Conservation Division Agent