



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date 1 September, 19 58, authorized the following plugging operation:

Operator's Full Name: Shell Oil Co.

Complete Address: Box., 744, Great Bend, Kans.

Lease Name: Hoeme Well No. 3

Location: SW NW NW Sec. 28 Twp. 26 Rge. 12 (E) (W) X

County: Pratt Total Depth: 4312

Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

806' of 8 5/8" surface casing circulated with cement. Sand hole to 3696 and dump 5 sack cement top perf. Pull pipe and mud hole to 300'. Set rock bridge at 300' with 20 sack cement top bridge. Heavy mud to 35'. Rock bridge and cement to base of cellar.

Very truly yours,

Signed: [Signature] Conservation Division Agent

RECEIVED STATE CORPORATION COMMISSION

SEP 20 1958 9-20-58 CONSERVATION DIVISION