

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 27 Twp. 32S Rge. 15W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

SE NE NE
Lease Owner Raymond Oil Company, Inc.
Lease Name Hildebrand Well No. 6

Office Address 200 West Douglas, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____

Injection Well
Date Well completed _____ 19____
Application for plugging filed _____ 5-31 1977
Application for plugging approved Renewed Appr. 11-22 1977
Plugging commenced _____ 11-22 1977
Plugging completed See below _____ 8-1 1978
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

Depleted
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4911
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	400	None
				5-1/2	4902	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

11-22-77 Cemented w/250 sacks (175 common, 75 -50-50 Poz. Mixed 4 sacks hulls and 25 sacks gel ahead of cement.
8-1-78 Cemented w/100 sacks additional (50 common - 50 Poz.)
Pumped cement on both sides of casing until it was filled to surface.

Plugging complete.
(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementing Co., Inc.
P. O. Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.
Pat R. Raymond (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Pat R. Raymond
RAYMOND OIL COMPANY, INC.
200 West Douglas, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of September, 1978

My commission expires March 22, 1979

Kathleen Pipes
Kathleen Pipes Notary Public.
STATE CORPORATION COMMISSION

SEP 27 1978
9-17-78
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas

COPY


15-007-1034-00-01

Company - CHAMPLIN REFG. CO.
Farm - Hildebrand No. 6

SEC. 27 T. 32 R. 15 W
SE NE NE
990' FNL & 330' FEL NE 1/4

Total Depth. 4911'
Comm. 10-24-44 Comp. 12-12-44
Shot or Treated.
Contractor.
Issued. 7-7-45

County. Barber
KANSAS



CASING:

10 3/4" 400' Cem.
5 1/2" 4902' Cem.

w/250
w/200

Elevation. _____

Production. 10,000,000 G.

Figures Indicate Bottom of Formations.

lime rock	0-80
red bed	690
red bed & shale shells	960
shale & lime shells	1755
shale & lime	2010
lime	2410
lime sdy	2500
lime	2910
lime w shale	2980
lime	3110
lime & shale	3445
lime	3500
lime & shale	3700
shale	3730
shale & lime	3845
shale	3960
lime	4045
shale & lime	4110
shale	4130
sand	4160
lime	4220
lime hrd	4270
lime	4660
shale	4703
shale & lime	4738
shale	4772
lime	4802
shale	4842
lime	4906
Cored & reamed	4911
Total Depth	

Tops:

Florence flint	2478
Lansing	4162
Mississippian	4694
Viola	4882

RECEIVED
STATE CORPORATION COMMISSION

JUN 02 1977
6-2-77
CONSERVATION DIVISION
Wichita, Kansas